ABBREVIATIONS

A	AREA OR ARC
A.D.	ALGEBRAIC DIFFERENCE
AASHTO	AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTAIONS OFFICIALS
Ac.	ACRE
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
APPROX.	APPROXIMATE
ARCH	ARCHITECTURAL
ARV	AIR RELEASE VALVE
ASPH	ASPHALT
BB	BOTTOM OF LINE
BC	BOTTOM OF CURB
BF	BASEMENT FLOOR
BGW	BEGINNING OF WALL
BLDG	BUILDING
BM	BENCH MARK
BOV	BLOW OFF VALVE
BRL	BUILDING RESTRICTION LINE
BVCS	BEGINNING VERTICAL CURVE STATION
BVCE	BEGINNING VERTICAL CURVE ELEVATION
BW	BOTTOM OF WALL
C	COEFFICIENT OF RUNOFF
CATV	CABLE TELEVISION
CB	CHORD BEARING
C.B.	CATCH BASIN
CC	CENTER TO CENTER
CFS (Q)	CUBIC FEET PER SECOND
C&G	CURB AND GUTTER
CH	CHORD
C.I.P.	CAST IRON PIPE
℄	CENTERLINE
CL	CLASS
CMP	CORRUGATED METAL PIPE
CONC.	CONCRETE
CO	CLEAN OUT
COMM	COMMUNICATIONS CABLE
CT	COURT
CONT.	CONTINUATION
d	DEPTH
DA	DRAINAGE AREA
DB	DEED BOOK
DET.	DETAIL
DI	DROP INLET
DIA	DIAMETER
DIP	DUCTILE IRON PIPE
DM	DROP MANHOLE
DR.	DRIVE
DWG	DRAWING
D/W	DRIVEWAY
E	ELECTRICAL
EC	EROSION CONTROL
ESM'T	EASEMENT
EG	EDGE OF GUTTER
ELEV.	ELEVATION
E.P.	EDGE OF PAVEMENT
ES	END SECTION
EW	END WALL
EX.	EXISTING
EBL	EAST BOUND LANE
FAR	FLOOR AREA RATIO
F.C.	FACE OF CURB
FM	FORCE MAIN
FT.	FEET
FF	FIRST FLOOR
FG	FINISHED GRADE
FH	FIRE HYDRANT
FP	FLOOD PLAIN
FOY.	FOYER
FPS	FEET PER SECOND
G	GAS
GFA	GROSS FLOOR AREA
Gr.	GRADE
G.R.	GUARD RAIL
HC	HANDICAPPED PARKING SPACE
HDPE	HIGH DENSITY POLYETHYLENE
HGL	HYDRAULIC GRADE LINE
HORIZ. OR HRZ.	HORIZONTAL
HP	HIGH POINT
HR	HAND RAIL
HT.	HEIGHT
I	RAINFALL INTENSITY
ID	INSIDE DIAMETER
IN	INCH
INV.	INVERT
IP	IRON PIPE
IPF	IRON PIPE FOUND
IPS	IRON PIPE SET
JB	JUNCTION BOX
K.	RATE OF VERTICAL CURVATURE
L	LENGTH
LAT.	LATERAL
LL	LOWER LEVEL
LOC.	LOCATION
LP	LIGHT POLE
L.P.	LOW POINT
L.S.	LOADING SPACE
LCG	LIMITS OF CLEARING & GRADING
M	MONUMENT FOUND
MECH.	MECHANICAL
MH	MANHOLE
MI	MILE
MS	MEDIAN STRIP
MSL	MEAN SEA LEVEL
N/F	NOW OR FORMERLY
NFA	NET FLOOR AREA
No. OR #	NUMBER
NBL	NORTH BOUND LANE
OC	ON CENTER
OD	OUTSIDE DIAMETER
OH	OVERHANG
PC	POINT OF CURVATURE
PCC	POINT OF COMPOUND CURVE
PCEP	POINT OF CURVE EDGE OF PAVEMENT
PCTC	POINT OF CURVATURE TOP OF CURB
PG.	PAGE
PGL	POINT OF GRADE LINE
PI	POINT OF INTERSECTION
P/L	PROPERTY LINE
PRC	POINT OF REVERSE CURVE
PRELIM.	PRELIMINARY
PROP.	PROPOSED
PT	POINT OF TANGENCY
PVC	POLYVINYL CHLORIDE
PVI	POINT OF VERTICAL INTERSECTION
PVM'T	PAVEMENT
PVT	POINT OF VERTICAL TANGENT
P&P	PLAN AND PROFILE
Q	RUNOFF FLOW RATE CFS
R	RADIUS
REQ'D	REQUIRED
RESTR.	RESTRAINED
RCP	REINFORCED CONCRETE PIPE
RD.	ROAD
RET.	RETAINING
REV.	REVISION
RR	RAILROAD
RTE.	ROUTE
R/W	RIGHT OF WAY
RGP	ROUGH GRADING PLAN
SAN.	SANITARY
SBL	SOUTH BOUND LANE
SD	SIGHT DISTANCE
SECT.	SECTION
SEW.	SEWER
SF	SQUARE FEET
SP	SITE PLAN
SPEC.	SPECIFICATION
STA.	STATION
STD.	STANDARD
STK.	STACK
STM.	STORM
SVC.	SERVICE
S/W	SIDEWALK
SWM	STORMWATER MANAGEMENT
Sx	CROSS SLOPE
T.	TANGENT
TB	TEST BORE
TC	TOP OF CURB
TEL	TELEPHONE
TP	TEST PIT
TOB	TOP OF BANK
TW	TOP OF WALL
UD	UNDER DRAIN
UG	UNDERGROUND
UGE	UNDERGROUND ELECTRICAL CABLE
UL	UPPER LEVEL
UP	UTILITY POLE
V	VELOCITY
VA	VIRGINIA
VC	VERTICAL CURVE
VDOT	VA. DEPT. OF TRANSPORTATION
VERT.	VERTICAL
VF	VERTICAL FEET
VTM	VIRGINIA TEST METHOD
W OR WTR	WATER
W/M	WATER MAIN
WBL	WEST BOUND LANE
WSE	WATER SURFACE ELEVATION
X-ING	CROSSING
YD	YARD
YI	YARD INLET
YR	YEAR
Z	SIDE SLOPE HORIZONTAL RATIO
Z.O.	ZONING ORDINANCE

EMERGENCY CONTACT PHONE NUMBERS

COMPANY	NUMBER
COLUMBIA GAS OF VIRGINIA	1-800-543-8911
COLUMBIA GAS TRANSMISSION CORP.	1-800-835-7191(24HRS); 1-800-876-4568
LOUDOUN COUNTY SANITATION AUTHORITY	703-771-1092; AFTER HOURS 703-729-7878
LOUDOUN HOSPITAL CENTER	703-858-6000
MISS UTILITY	1-800-552-7001
WASHINGTON GAS	703-750-1000; 1-800-752-7520; GAS LEAK 703-750-4831
NORTHERN VIRGINIA ELEC. CO-OP	703-335-0500; 703-631-9873
OFFICE OF SOLID WASTE MANAGEMENT	703-777-0187
POLICE	911
TRANSCO GAS PIPELINE CO.	1-410-465-0960 (24 HRS)
VERIZON	703-954-6611 OR 703-954-6707 (24 HRS)
DOMINION VIRGINIA POWER	1-888-667-3000 OR 703-359-3000

OSWM PERSONNEL EMERGENCY CONTACT PHONE NUMBERS

RICK WEBER, DIRECTER, OSWM	OFFICE: 703-777-0187 PAGER: 703-737-4171 CELL: 540-336-3365 HOME: 540-837-1252
MICHAEL FAIRBANKS, MANAGER OF LANDFILL OPERATIONS	OFFICE: 703-777-0168 CELL: 703-209-8172 HOME: 540-822-4878
JAMES WHITE, FACILITIES FIELD SUPERVISOR	OFFICE: 703-737-8982 CELL: 703-401-9470 HOME: 301-834-4637
DON BREDICE, PROJECT ENGINEER	OFFICE: 703-737-8678 CELL: 703-401-6405 HOME: 703-771-9675
KEVIN QUESENBERRY, ON-SITE SAFETY REPRESENTATIVE	OFFICE: 703-737-8827 HOME: 703-777-1819
TODD JACKSON, ON-SITE SAFETY REPRESENTATIVE	OFFICE: 703-737-8827 HOME: 540-722-9705

LEGEND

EXISTING INTERMEDIATE CONTOUR
EXISTING INDEX CONTOUR
PROPOSED INTERMEDIATE CONTOUR
PROPOSED INDEX CONTOUR
EXISTING EDGE OF PAVEMENT
PROPOSED EDGE OF PAVEMENT
PROPOSED HEADER CURB (CG-2)
EXISTING CURB
EXISTING CURB & GUTTER
PROPOSED CURB & GUTTER (CG-2) W/ 5' CONC. S/W
TRANSITION FROM CG-6-CG-6R
EXISTING STORM SEWER W/INLET
PROPOSED STORM SEWER W/INLET
EXISTING SANITARY SEWER W/MH
PROPOSED SANITARY SEWER W/MH
PROPERTY LINE
EXISTING EASEMENT
PROPOSED EASEMENT
CENTER LINE
EXISTING SPOT ELEVATIONS
PROPOSED SPOT ELEVATION
EXISTING TREE LINE
EXISTING TREE W/TRUNK DIAMETER
EXISTING TREE W/DRIPLINE
PROPOSED TREE
FLOW LINE OF SWALE/DITCH
FLAT BOTTOM DITCH
EXISTING FENCE LINE
PROPOSED FENCE LINE
LIMITS OF CLEARING & GRADING
EXISTING UTILITY POLE
PROPOSED UTILITY POLE
EXISTING FIRE HYDRANT (WITH "T" AND VALVE)
PROPOSED FIRE HYDRANT (WITH "T" AND VALVE)
HANDICAP RAMP DENOTES LOCATION OF STD. CSRP-1
PARKING INDICATOR INDICATES THE NUMBER OF PARKING SPACES
STOP SIGN

TEST PIT
TELE. JUNCTION BOX
ELEC. TRANSFORMER
EXISTING STORM SEWER LABEL
PROPOSED STORM SEWER LABEL
EXISTING SIGN
EXISTING STREET LIGHT
PROPOSED STREET LIGHT
PROPOSED LIGHT POLE
BUILDING ENTRANCE
BENCH MARK
PROPOSED WATERLINE
PROPOSED WATERLINE GATE VALVE
PROPOSED WATERLINE CROSS
PROPOSED WATERLINE TEE
PROPOSED WATERLINE 90° BEND
PROPOSED WATERLINE 45° BEND
PROPOSED WATERLINE 22 1/2° BEND
PROPOSED WATERLINE 11 1/4° BEND
PROPOSED WATERLINE REDUCER
EXISTING WATERLINE W/TEE
EXISTING WATER VALVE
EXISTING REDUCER
EXISTING TELEPHONE LINE
PROPOSED TELEPHONE LINE
EXISTING ELECTRIC SERVICE
PROPOSED ELECTRIC SERVICE
EXISTING GAS LINE
PROPOSED GAS LINE
WATER METER (SINGLE & DOUBLE)
PROPOSED WATERLINE W/ 2" BLOW-OFF VALVE
PROPOSED FLOODPLAIN
EXISTING FLOODPLAIN
RPA BUFFER LIMITS

NOTES:

1. EXISTING STRUCTURES AND FACILITIES ARE SHOWN LIGHT-LINED OR SCREENED. NEW STRUCTURES AND FACILITIES ARE SHOWN HEAVY-LINED.

2. THIS IS A STANDARD LEGEND DRAWING. SOME SYMBOLS OR ABBREVIATIONS MAY APPEAR ON THIS DRAWING AND MAY NOT BE USED IN THIS PROJECT.

LCSA STANDARD NOTES

1. ALL WATER MAINS AND SANITARY SEWERS MUST BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT LCSA STANDARDS AND SPECIFICATIONS.

2. NO BLASTING IS PERMITTED WITHIN 25' OF EXISTING LCSA UTILITIES.

3. WATER SERVICES MUST MAINTAIN A MINIMUM 6' HORIZONTAL SEPARATION FROM SANITARY LATERALS.

4. ALL LCSA SANITARY AND WATER MAIN EASEMENTS MUST BE 10', UNLESS OTHERWISE NOTED.

5. SANITARY SEWERS AND WATER MAINS TRAVERSING LOT LINES MUST MAINTAIN A MINIMUM 15' HORIZONTAL SEPARATION FROM PROPOSED OR EXISTING BUILDINGS, UNLESS PRIOR PERMISSION IS GRANTED BY LCSA.

6. ALL HYDRANTS AND METER CROCKS MUST MAINTAIN 5' HORIZONTAL SEPARATION FROM EDGE OF DRIVEWAY APRONS.

7. WATER MAINS MUST MAINTAIN A MINIMUM 5' HORIZONTAL SEPARATION FROM EDGE OF GUTTER PAN, EXCEPT AT DESIGNATED CROSSINGS.

8. LANDSCAPING IS NOT PERMITTED WITHIN LCSA EASEMENTS, OR WITHIN 5' OF FIRE HYDRANTS AND METER LOCATIONS.

9. ALL WATER MAINS MUST BE CLASS 52 DUCTILE IRON PIPE, UNLESS OTHERWISE NOTED.

10. A 2" DETECTABLE MARKING TAPE MUST BE PLACED ABOVE ALL WATER MAINS OUTSIDE OF PAVEMENT.

11. ALL SANITARY SEWERS MUST BE PVC DR-25 PER AWWA-C900, UNLESS OTHERWISE NOTED.

12. ALL SANITARY SEWER LATERALS MUST BE 4" PVC AT 2.08% SLOPE UNLESS OTHERWISE NOTED AND MUST ENTER THE MAIN AT 90 DEGREES.

13. A 2" DETECTABLE MARKING TAPE MUST BE PLACE ABOVE ALL PVC SANITARY SEWERS.

14. PROVIDE POSITIVE DRAINAGE FOR SANITARY MANHOLES LOCATED OUTSIDE OF PAVEMENT AREAS.

15. TOP OF MANHOLES LOCATED OUTSIDE OF PAVEMENT AREAS MUST BE 1' ABOVE FINISHED GRADE. THIS REQUIREMENT SHALL NOT APPLY IN DEVELOPED LAWNS.

16. EXISTING SANITARY MANHOLE SHALL BE CORE BORED IN ORDER TO RECEIVE PROPOSED PIPE.

17. UTILITIES OUTSIDE OF THE PUBLIC RIGHT-OF-WAY SHALL BE PROVIDED WITH ABOVE GROUND MARKING STAKES, SPACED EVERY 100 FEET.

PROJECT SCOPE OF WORK:

THIS PROJECT INVOLVES THE CONSTRUCTION OF NEW LEACHATE PUMP STATIONS, VALVE VAULT, FLOW METER VAULT WITH ASSOCIATED ELECTRICAL AND LOW VOLTAGE DISTRIBUTION AND SCADA SYSTEM. THE PROJECT ALSO INCLUDES THE INSTALLATION OF APPROXIMATELY 50 FEET OF 3 INCH HDPE FORCE MAIN PIPING CONNECTED TO AN EXISTING 3" FORCEMAIN PIPE AND THE CONSTRUCTION OF APPROXIMATELY 150 FEET OF 4" HDPE PIPE TO THE EXISTING T-3 TANK.

CONSTRUCTION NOTE

UTILITIES

UTILITY LOCATIONS SHOWN ARE APPROXIMATE, CONTRACTOR SHALL BE REQUIRED TO FIELD VERIFY UTILITY LOCATIONS PRIOR TO EXCAVATION. THE CONTRACTOR SHALL CONTACT MISS UTILITY AT 1-800-257-7777 PRIOR TO COMMENCEMENT OF ANY EXCAVATION.

WHERE EXISTING UNDERGROUND UTILITIES OR OTHER STRUCTURES APPEAR TO BE IN CLOSE PROXIMITY TO PROPOSED CONSTRUCTION, OR WHEN APPROACHING EXISTING UTILITIES OR STRUCTURES FOR CROSSINGS OR CONNECTIONS, THE TRENCH SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK, OR TEST PITS MADE, TO VERIFY EXACT LOCATION, SIZE AND INVERT OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN LINE OR GRADE. ANY NECESSARY CHANGES IN LINE, GRADE, OR MATERIAL CAUSED BY FAILURE TO TAKE SUCH PRECAUTIONS SHALL BE AT THE EXPENSE OF THE CONTRACTOR. MINOR CHANGES IN ALIGNMENT OR DEPTH OF EXCAVATION SHALL BE DONE AT NO ADDITIONAL COST.

THE CONTRACTOR SHALL FIELD VERIFY THE LOCATION AND DIMENSION OF ALL EXISTING PIPING, STRUCTURES AND EQUIPMENT, PRIOR TO ORDERING AND INSTALLING NEW EQUIPMENT OR PIPING.

ALL CONSTRUCTION METHODS AND MATERIALS SHALL BE IN ACCORDANCE WITH THE LOUDOUN COUNTY SANITATION AUTHORITY "SANITARY SEWER SYSTEM - STANDARDS AND EXTENSIONS" DATED NOVEMBER 6, 1990. ANY CONTRACTOR INVOLVED IN THE BID AND/OR CONSTRUCTION OF PUBLIC FACILITIES FOR LOUDOUN COUNTY SANITATION AUTHORITY SHALL BECOME FAMILIAR WITH THESE STANDARDS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UTILITY RELOCATION REQUIRED AS PART OF THIS WORK.

IF ADDITIONAL UTILITIES NOT SHOWN ON THE PLANS ARE LOCATED BY MISS UTILITY AND THEY CROSS THE PROPOSED UTILITY LINE THE CONTRACTOR SHALL TEST PIT THESE LOCATIONS.

PROPOSED ELECTRICAL SERVICE CONNECTION TO THE MODULAR BUILDING SHOULD BE FURNISHED AND INSTALLED IN COMPLIANCE WITH ALL APPLICABLE NEC AND VDOT CODES AND SPECIFICATIONS.

THE CONTRACTOR SHALL NOT IN ANY WAY INTERFERE WITH OR IMPACT ANY OPERATIONS OF THE ACTIVE LANDFILL. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING OR RECTIFYING ANY IMPACTED LANDFILL OPERATIONS IMMEDIATELY AS DIRECTED BY THE OWNER.

GENERAL

THE CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ALL DIMENSIONS AND TO PREPARE SHOP DRAWINGS ACCORDINGLY BEFORE SUBMITTING DRAWINGS FOR APPROVAL. NO MATERIALS OR EQUIPMENT SHALL BE ORDERED OR FABRICATED PRIOR TO SHOP DRAWING APPROVAL. SHOP DRAWING APPROVAL SHALL NOT RELIEVE THE CONTRACTOR OF ANY OBLIGATIONS TO PROVIDE A COMPLETE AND FUNCTIONAL SYSTEM.

THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO EXISTING ROADS, UTILITIES, PIPING, STRUCTURES, FENCING AND EQUIPMENT WHICH OCCURS AS A RESULT OF HIS WORK ON THIS PROJECT.

FILL SHOULD BE COMPACTED IN LIFTS NOT EXCEEDING 8 INCHES IN LOOSE THICKNESS TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY PER VTM-1 (ASTM D-698). THE UPPER 6 INCHES OF PAVEMENT SUBGRADES SHOULD BE COMPACTED TO AT LEAST 100% OF THE MAXIMUM DRY DENSITY PER VTM-1 (ASTM D-698).

PAVEMENT SUBGRADES SHOULD BE PROOF ROLLED WITH A 10-TON LOADED DUMP TRUCK OR OTHER EQUIVALENT WEIGHT RUBBER-TIRED CONSTRUCTION EQUIPMENT IMMEDIATELY PRIOR TO PLACING STRUCTURAL FILL OR STONE BASE COURSE MATERIAL.

GENERAL NOTES

1. THE PROPERTY DELINEATED ON THIS PLAN IS LOCATED ON LOUDOUN COUNTY PIN NUMBERS AS SHOWN ON THE PLANS, AND IS OWNED BY LOUDOUN COUNTY VIRGINIA BY DEEDS AS SHOWN ON THE PLANS. THE PROPERTY IS ZONED AR-1 UNDER THE REVISED 1993 ZONING ORDINANCE.
2. TOPOGRAPHIC INFORMATION DEPICTED HEREON TAKEN FROM INFORMATION FROM TOPOGRAPHIC SURVEY PERFORMED BY DEWBERRY SURVEYS 2007, AND THE CONTROL DATA IS NAD 27 ALSO BY DEWBERY SURVEYS 2007.
3. THE LOUDOUN COUNTY LANDFILL ADDRESS IS 20939 EVERGREEN MILLS ROAD, LEESBURG, VIRGINIA 20175.
4. ACCORDING TO LOUDOUN COUNTY MAPPING, THERE IS A MINOR FLOODPLAIN ON THE LOUDOUN COUNTY SCHOOL BOARD PROPERTY.
5. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PROVIDED IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.
6. THE PURPOSE AT THIS PLAN IS TO PROVIDE A LEACHATE PUMP STATION AND FORCE MAIN.
7. ALL EXISTING STRUCTURES, TANKS FARM DUMPS, ETC SHALL BE CAREFULLY REMOVED AND DISPOSED OF AT A LOUDOUN COUNTY APPROVED WASTE DISPOSAL SITE IN ACCORDANCE WITH APPLICABLE REGULATIONS.
8. LANDSCAPING FOR THIS SITE SHALL BE SUBJECT TO SECTION 5-1300 OF THE LOUDOUN COUNTY ZONING ORDINANCE.
9. THIS SITE DOES NOT CONTAIN CLASS III AND/OR CLASS IV SOILS, PER THE LATEST COUNTY SOILS MAP AND AS IDENTIFIED IN THE UINTERPRETIVE GUIDE TO SOILS MAP, LOUDOUN COUNTY, VIRGINIA.
10. THERE ARE NO KNOWN ARCHEOLOGICAL, NATURAL AND HISTORIC FEATURES, CEMETERIES, OR HISTORIC LANDMARKS ON THE AFOREMENTIONED SITE IN ADOPTED FEDERAL AND STATE DOCUMENTS.
11. STORMWATER MANAGEAMENT AND BMP'S FOR THIS SITE ARE NOT REQUIRED WITH THE PROPOSED PLAN. THE PLAN PROPOSES NO INCREASE IN SITE IMPERVIOUS AREA.
12. ALL CONSTRUCTION SHALL CONFORM TO CURRENT LOUDOUN COUNTY AND VDOT STANDARDS AND SPECIFICATIONS.
13. THE APPROVAL OF THESE PLANS SHALL IN NO WAY RELIEVE THE DEVELOPER OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA OR ANY OTHER ORDINANCE ENACTED BY LOUDOUN COUNTY.
14. THE APPROVAL OF THESE PLANS SHALL IN NO WAY RELIEVE THE DEVELOPER OR HIS AGENT FROM COMPLYING WITH OTHER APPLICABLE LOCAL, STATE OR FEDERAL REQUIREMENTS.
15. APPROVAL OF THESE PLANS SHALL IN NO WAY GRANT PERMISSION BY THE COUNTY FOR THE DEVELOPER TO TRESSSPASS ON OFFSITE PROPERTIES.
16. CONTRACTOR SHALL NOT IN ANY WAY INTERFERE WITH OR IMPACT ANY OPERATIONS OF THE ACTIVE LANDFILL. CONTRACTOR IS RESPONSIBLE FOR REPAIRING OR RECTIFYING ANY IMPACTED LANDFILL OPERATIONS IMMEDIATELY AS DIRECTED BY THE OWNER.

Dewberry

Dewberry & Davis LLC
8401 ARLINGTON BLVD.
FAIRFAX, VA 22031
PHONE: 703.849.0100
FAX: 703.849.0118

LOUDOUN COUNTY SOLID WASTE MANAGEMENT FACILITY

LEACHATE PUMP STATIONS & FORCE MAIN

LOUDOUN COUNTY, VIRGINIA

SEAL

COMMONWEALTH OF VIRGINIA
JEFFREY B. CHAPIN
Lic. No.9519
4/10/09
PROFESSIONAL ENGINEER

SCALE

No.	DATE	BY	Description

REVISIONS

DRAWN BY	YR
APPROVED BY	ARM
CHECKED BY	JBC
DATE	4/7/09

TITLE

GENERAL NOTES, ABBREVIATIONS & SYMBOLS

PROJECT NO. 50006147

G-02

SHEET NO. 2 OF 12

S:\Loudoun\Leachate Forcemain\Construction plans\Pump stations\02 G-02-REV.dwg Dec 08, 2009 - 2:21pm