SURVEYED BY_____
SUPERVISED BY_____
DESIGNED BY_____

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

REVISED	STATE	FEDERAL AID PROJECT	STATE ROUTE	STATE PROJECT	SHEET NO.
NEW 10/22/08	VA.		7		20

UTILITY RELOCATION SUMMARY

PROJECT NO.	Sheet Number	Communication Conduit Bundle, 1-5"-8" Way (Woodlawn)	Communication Conduit Bundle, 4-4" Way (Verizon)	Communication Conduit Bundle, 2-4" Way (RGC/Yipes)	Communication Conduit Bundle, 2-3" Way (MCI/VB)	Communication Conduit Bundle, 1-5"-28" Way (Level 3)	Communication Conduit Bundle, 1-5"-4" Way (XO)					Communication Vault 6' x 7' x 12'	Communication Vault 4' x 4' x 4'	Communication Vault 4' x 6' x 4'				Handhole 3' x 5' x 3'	Handhole 3' x 4' x 3'	Pedestals 3' x 1' x 3' *	
		LF.	LF.	LF.	LF.	LF.	LF.					EA.	EA.	EA.				EA.	EA.	EA.	
	TOTAL	3,010	4,110	2,210	3,000	2,629	2,489					3	5	6				27	12	2	

* NOT A PAY ITEM. SEE NOTE 6 FOR DETAILS

GENERAL NOTES :

1. ALL COMMUNICATION CONDUIT WORK SHOWN ON THESE UTILITY RELOCATION PLANS ARE BEING CONSTRUCTED FOR USE OF VERIZON, RGC/YIPES, LEVEL 3, XO, MCI / VERIZON BUSSINESS (COMMUNICATION COMPANIES). THE CONTRACTOR MAY CONSULT WITH THEIR REPRESENTATIVES AT THE FOLLOWING PHONE NUMBERS TO OBTAIN ADDITIONAL TECHNICAL INFORMATION:

   WOODLAWN: BUD CASPARI - (571) 236-0073
   RENEE CHUBBS [ON-TIME UTILITY SOLUTIONS] - (703) 788-1533

   RGC/YIPES: JAMES HOOFNAGLE -(202) 216-7865
   TONY MACK [MACK COMM.] - (703) 867-1741

   VERIZON: JERRY BROWN - (540) 359-5207
   JIM TEMPLE - (540) 359-5206

   LEVEL 3: JODY WILLIAMS - (703) 673-7520

   XO: MARK JOHNSON [EXPRESS TECHNOLOGIES] - (540) 752-6691

   MCI / VERIZON BUSINESS: ADAM RICE - (571) 220-8978

2. LOCATION OF EXISTING UTILITIES SHOWN IS APPROXIMATE AND MAY BE INCOMPLETE. CONTRACTOR SHALL FIELD VERIFY LOCATION AND DEPTH OF UTILITIES WITH TEST HOLES AND/OR OTHER METHODS. TEST HOLES, TEST PITS, OR OTHER METHODS TO VERIFY LOCATION AND DEPTH OF EXISTING UTILITIES IS INCIDENTAL TO THE WORK AND SHALL BE INCLUDED IN THE PRICE BID FOR OTHER CONTRACT ITEMS.

3. THE CONTRACTOR SHALL PLAN AND SCHEDULE ALL CONTRACT WORK TO ACCOMODATE THE LOCATION OF ALL EXISTING OVERHEAD COMMUNICATION LINES AND UNDERGROUND DUCT BANKS OF THE COMMUNICATION COMPANIES. THE CONTRACTOR SHALL ARRANGE FOR ANY REQUIRED TEMPORARY OUTAGES TO ACCOMMODATE THE CONTRACTOR'S WORK. SHOULD THE CONTRACTOR WISH TO TEMPORARILY RELOCATE ANY OF THE COMMUNICATION COMPANIES FACILITIES, IT SHALL BE DONE SOLELY AT THE CONTRACTOR'S EXPENSE. ANY REQUESTS FOR TEMPORARY UTILITY RELOCTIONS, SHALL BE SUBMITTED IN WRITING TO THE ENGINEER 30 DAYS IN ADVANCE OF ANY WORK COMMENCING TO RELOCATE FACILITIES. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO FULLY COORDINATE ANY REQUESTED OUTAGES AND/OR TEMPORARY RELOCATIONS WITH AFFECTED PARTIES.

4. THE COST FOR DUCT BANK SHALL INCLUDE BUT NOT BE LIMITED TO (AMONG OTHER ITEMS LISTED IN THE SPECIAL PROVISIONS) SAWCUTTING, DEMOLITION, REMOVAL, DISPOSAL AND RESTORATION OF CURBS, SIDEWALKS, TRAILS AND PAVEMENT STRUCTURES (FLEXIBLE AND RIGID) WITHIN THE LIMITS AND TYPES SHOWN ON THE PLAN.

5. THE COMMUNICATIONS COMPANIES ARE RESPONSIBLE FOR REMOVAL OF EXISTING OVERHEAD CABLE ONCE THE CUTOVER IS COMPLETE.

6. THE COMMUNICATION COMPANIES SHALL PROVIDE THE CONTRACTOR 30 INCH FRAME AND COVERS FOR ALL PROPOSED VAULTS AND PEDESTALS. THE CONTRACTOR SHALL ALLOW 30 DAYS LEAD TIME TO ORDER AND OBTAIN FRAME AND COVERS. AND PEDESTALS FROM THE COMUNICATION COMPANIES. COST TO INSTALL AND OBTAIN FRAME AND COVER. AND PEDESTALS SHALL BE INCLUDED IN THE BID PRICE FOR THE COMMUNICATION CONDUIT BUNDLE AND COMMUNICATION VAULT. SEE COMMUNICATION DUCT BANK SPECIAL PROVISION.

7. FOR A LIST OF APPROVED CONTRACTORS SEE SPECIAL PROVISION FOR COMMUNICATION DUCT BANK.

8. MARKING TAPE SHALL BE PLACED 12 INCHES ABOVE TOP OF CONDUITS FOR ALL CONDUIT BUNDLES.

express-tek
EXPRESS TECHNOLOGIES, INC.
1127 INTERNATIONAL PARKWAY SUITE 293
FREDERICKSBURG, VA 22406
540.752.6691 (O) 540.752.6694 (F)

OUS ON-TIME UTILITY SOLUTIONS, LLC
44330 MERCURE CIRCLE, SUITE 140
DULLES, VIRGINIA 20166

COMM. UTILITY RELOCATION PLAN
GENERAL NOTES AND SUMMARY

PLAN NO.	PROJECT	FILE NO.	SHEET NO.
			20