

## GENERAL NOTES:

7. ALL TV'S AND MONITORS SHALL BE PROVIDE WITH WESTNET VMSS BOX AND COAX CABLE OUTLETS TO ALL TV'S AND MONITORS EXCEPT IN THE APPARATUS BAY, MONITORS REQUIRE ONLY VMSS. SEE DRAWINGS T4-1, T4-2 AND T4-3 FOR ADDITIONAL INFORMATION.
8. ALL CATV AND MONITOR LOCATIONS SHALL HAVE SINGLE GANG COVER PLATE WITH PUSH HOLE AND PULL STRING FOR COAX CABLING.
9. G.C. IS RESPONSIBLE FOR PROVIDING ALL OUTLETS, CABLING, CONDUITS, AND CONNECTIONS FOR A COMPLETE FUNCTIONAL CATV SYSTEM.
10. WIRELESS ACCESS POINT DEVICES WILL BE PROVIDED BY THE COUNTY. G.C. LOW VOLTAGE CONTRACTOR IS RESPONSIBLE FOR ALL ASSOCIATED CAT6 CABLING INCLUDING CABLE AND CABLE RUNS BACK TO SERVICING CLOSET AS COORDINATED WITH THE OWNER. FINAL CONNECTIONS AND TERMINATION'S TO DEVICES AND EQUIPMENT WILL BE PROVIDED BY THE COUNTY.

1

## FIRST FLOOR PLAN – TELECOM

SCALE: 1/8" = 1'-0"

 ADDENDUM 2 03-21-11

DRAWING REFERENCE: T3.1

**BRINJAC**

ENGINEERING  
since 1955

114 North 2nd Street  
Harrisburg, PA 17101-1401  
Phone: (717) 233-4502  
Fax: (717) 233-0833  
www.brinjac.com

FIRST FLOOR PLAN - TELECOM

DRAWN BY:

KWW

DATE:

03/21/11

DRAWING NO:

TSK-2

CHECKED BY:

JLS

SCALE:

AS NOTED