

DENOTES LIGHTED

\ DENOTES LIGHTED

RGENCY LIGHTING

TER INDICATES

CH. LOWER CASE

TER INDICATES

ER INDICATES

ER INDICATES

EMA CONFIGURATION
RE SIMILAR NEMA



MOTION SENSOR



ELECTRIC DEADBOLT



EXIT BUTTON



REQUEST-TO-EXIT



SPEAKER



ALARM SIGNAL



STRUCK



VALVE TAMP

VOICE / DATA

CONTRACTOR SHALL PROVIDE ALL CABLING IN COMPLIANCE WITH THE LOUDOUN COUNTY CABLING STANDARDS. TERMINATE CABLES AT WALL OUTLETS AND IN THE IT CLOSET. PROVIDE ADEQUATE CABLE LENGTH IN IT CLOSET TO ALLOW CONNECTIONS TO COUNTY FURNISHED EQUIPMENT. COORDINATE WITH COUNTY IT STAFF.



TELEPHONE OUTLET WITH ONE CAT-6 CABLE BACK TO IT CLOSET. PROVIDE 3/4" EC AND PULL WIRE IN INSULATED WALLS STUBBED UP TO CEILING. IN ALL OTHER WALLS PROVIDE PULL STRING ONLY.



TWO DATA OUTLETS WITH TWO CAT-6 CABLES BACK TO IT CLOSET. PROVIDE 3/4" EC AND PULL WIRE IN INSULATED WALLS STUBBED UP TO CEILING. IN ALL OTHER WALLS PROVIDE PULL STRING ONLY.



COMBINATION TELEPHONE/DATA OUTLET WITH TWO CAT-6 CABLES BACK TO IT CLOSET. PROVIDE 3/4" EC AND PULL WIRE IN INSULATED WALLS STUBBED UP TO CEILING. IN ALL OTHER WALLS PROVIDE PULL STRING ONLY.



EXISTING TELEPHONE OR DATA OUTLET. PROVIDE NEW OUTLET, FACEPLATE, AND CABLING AS DESCRIBED ABOVE.

SYMBOLS



CABLE



A/V JUNCTION



SPEAKER

ILLUMINAIRE SCHEDULE

USE POLE MOUNTED LIGHT AS ALTERNATE TO LT IF REQUESTED BY ARCHITECT

GENERAL NOTES (CONTINUED)

17. CONTRACTOR SHALL PROVIDE AND PAY FOR ALL ELECTRICAL SERVICE PRIMARY AND SECONDARY CONDUITS AND FEEDERS AND TRANSFORMERS. OWNER WILL ONLY BE RESPONSIBLE FOR ELECTRICAL CONNECTION FEE.
18. CONTRACTOR SHALL PROVIDE A COMPLETE CATV SYSTEM INCLUDING COAX CABLING AND OUTLETS. OWNER WILL ONLY BE RESPONSIBLE FOR UTILITY CONNECTION FEE.
19. COORDINATE ACTUAL POWER AND CONTROL POWER REQUIREMENTS FOR ALL EQUIPMENT WITH MANUFACTURER BEFORE INSTALLATION.
20. SEE DEMOLITION DRAWING D1.1 FOR AREAS BEING DEMOLISHED AS PART OF THIS PROJECT. REMOVE ALL RECEPTACLES, SWITCHES, AND LIGHT FIXTURES IN THESE AREAS AND REMOVE FEEDERS BACK TO SERVING PANEL.

GENERAL NOTES (CONTINUED)

21. BUILDING WILL REMAIN IN OPERATION AND ELECTRIC SERVICE MUST BE MAINTAINED DURING THE RENOVATION. OUTAGES SHALL BE LIMITED TO 4 HOURS AND COORDINATED WITH OWNER AT LEAST ONE WEEK IN ADVANCE. CONTRACTOR SHALL PROVIDE A TEMPORARY POWER SOURCE IF NECESSARY TO LIMIT OUTAGES TO 4 HOURS OR LESS.