



WINDOW ELEVATIONS
1/4" = 1'-0"

- WINDOW DETAIL NOTES:**
- 1] WEEP HOLE IN HEAD JOINT MIN 2 PER WINDOW
 - 2] FABRIC COATED COPPER THRU-WALL FLASHING WITH END DAMS
 - 3] BRICK HEADER COURSE SILL
 - 4] BACKER ROD & SEALANT - TYPICAL
 - 5] TREATED 2X CONTINUOUS NAILER
 - 6] SHIMS AS REQUIRED
 - 7] ALUM-CLAD WOOD CASEMENT WINDOWS
 - 8] WOOD EXTENSIONS BY MANUFACTURER - TYPICAL
 - 9] HARDWOOD CASING TRIM W/ EASED EDGES NOM 1" X 3" - TYPICAL
 - 10] 1 1/2" SOLID BLOCKING BY WINDOW MANUFACTURER
 - 11] ALUM CAP BY WINDOW MANUFACTURER
 - 12] ALUM-CLAD WOOD FIXED WINDOW
 - 13] 2" X 8" CONT NAILER AND BLOCKING WHERE CEILING IS SCHEDULED AT 8'-8 1/2" AFF
 - 14] FINISH CEILING SYSTEM REFER TO FINISH SCHEDULE FOR TYPE AND HEIGHTS
 - 15] FILL VOID WITH SPRAY APPLIED INSULATION - TYPICAL AROUND WINDOWS
 - 16] CEMENTITIOUS NOM 1" X 6" TRIM
 - 17] ALUM FLASHING SET-IN MASTIC TO SPRAY APPLIED AIR/VAPOR BARRIERS
 - 18] 2" METAL STUD
 - 19] 1" X 4" CEMENTITIOUS TRIM BOARD
 - 20] SPANDREL GLASS AT ABOVE-CEILING LOCATIONS
 - 21] 3/4" HARDWOOD
 - 22] 3/4" PLYWOOD
 - 23] ROLL-UP DOOR HOOD BY ROLL-UP DOOR MANUFACTURER
 - 24] GUIDE RAIL BY ROLL-UP DOOR MANUFACTURER - PROVIDE WOOD BLOCKING IN WALLS
 - 25] 3/4" HARDWOOD BEYOND
 - 26] ALIGN TO STOREFRONT MULLION
 - 27] CEMENTITIOUS PANEL
 - 28] SILL FLASHING
 - 29] 1 X 24 CEMENTITIOUS FRIEZE BOARD

HUGHES GROUP ARCHITECTS
22630 DAVIS DRIVE, SUITE 175
STERLING, VIRGINIA 20164
703.437.6600

CIVIL:
ALPHA ENGINEERING
21351 Ridgeway Circle, Suite 200
Sterling, VA 20166
(703) 450-0800

STRUCTURAL:
EHLERT-BRYAN
1451 Daley Madison Blvd, Suite 220
McLean, VA 22101
(703) 827-9552

MECHANICAL/ELECTRICAL:
BRINJAC ENGINEERING
4000 Albemarle Street, NW, Suite 305
Washington, DC 20016
(202) 237-2750

PURCELLVILLE FIRE AND RESCUE
500 MAPLE AVE. BUILDING #
PURCELLVILLE, VIRGINIA

WINDOW & LOUVER SCHEDULE AND DETAILS

KEY PLAN
N

REVISIONS:

NO.	DATE	DESCRIPTION
1	9-26-07	BID SET

STAMP AND SEAL:

DATE: 9-26-07 SCALE: AS NOTED

PROJECT NO. 0611

SHEET: A-631